

Causeways



The 45' x 7' barge sections are transported to the site on tractor-trailers, then assembled in the water.

A typical assembly will include a central moon-pool and double-drum winches to lift gates or other heavy items. Smaller anchor winches at each corner allow precise positioning of the barge over the work area.

A dive spread can be set up on the barge, including a Conex box, air compressor, hot water heater and pump, decompression chamber, generator, welder and communications equipment.